



- QTY.
- 1 1/2" PVC SLIP TEE
 - 1 1/2" PVC SST TEE
 - 2 1/2" PVC ST 90 ELLS
 - 1 GPH RISER ("A"), SEE BELOW
 - 2 GPH RISERS ("B"), SEE BELOW
 - 3 GPH EMITTERS
 - 3 #3 X 9" REBAR J-HOOK

- GPH ECO FLEX RISER ASSEMBLY PART# GECO(XX)
- #3 X 9" REBAR J-HOOK
- GPH PRESSURE COMPENSATING EMITTER, PART# GPST(X)
- TREE CANOPY
- TREE ROOTBALL

TREE SIZE	5 - 15 GAL.
NO. OF EMITTERS	3 EA.
RISER "A" (1)	GECO8
RISER "B" (2)	GECO12

EMITTERS SHALL BE INSTALLED AT EDGE OF TREE ROOTBALL AS SHOWN. ALL IRRIGATION EQUIPMENT SHALL BE INSTALLED PRIOR TO TREE LAYOUT AND PLANTING.
 COMPLETELY FLUSH CLEAN ALL PVC LATERAL LINES AND GECO RISERS BEFORE INSTALLATION OF EMITTERS.

